
Preceding work:

Operation no. of operation texts and work units or standard texts and flat rates: 07-1100



Coolant level	check, correct.
Engine oil level	check; pay attention to condition of oil (visual
	inspection).
Air filter element	remove, install (visual inspection).
Testers (001, 013, 017)	connect.
Pulse generator (021)	connect.
Accelerator control linkage	check ease of movement, condition. Lubricate
Full throttle stop	bearing points, relay levers, ball sockets. check from accelerator pedal, adjust Bowden cable if
	necessary.
Idle stop	check; adjust at Bowden cable if necessary.

Voltage at battery	test. Specification min. 11.5 volts.
Engine	warm up to operating temperature (coolant temperature approx. 80 °C).
Air conditioner or automatic climate control	switch off.
Idle speed	check, adjust if necessary. Unplug connector from actuator, plug in.
Start of delivery	test with digital tester.
Max. speed at no load	test.
Injection timer	test.
Electronic diesel system (EDS)	test with pulse counter (013), see (07.1-1120).
Anti-jerk control (ARA)	test with nulse counter (013) see (07.1-18/1)

Test and setting data

Engine	Idling speed in rpm with control	Idling speed in rpm without control connector at servomagnet unplugged	Start of delivery with digital tester RI specification	Max. speed without load or end of governed speed in rpm	Timing device w/o load or end of governed speed RIV meth. in°
602.96 1)	740±20	690±40	15±1° after TDC. I as of 09/89, Base version Code 62/0 as of 06/91, K ∨	5150±150	+3° to+5°
602.96 2)	680±20	620±40	B VV as of model year 1991: 14±0.5° after TDC.		
603.96	630±20 680±20 3)	570±40 620±40 3)	15±1° after TDC. Base version Code 62/0 as of 06/91, K ∨ as of model year 1991: 14±0.5° after TDC.		
603.970	630±20	570±40	15±1° after TDC. I as of 09/89: 14±0.5° after TDC.	4650±150	
603.971	610±20	560±40	14±0.5°	4750±150	


Manual transmission. Automatic transmission 4MATIC with manual transmission. 1) 2) 3)

Special tools










Commercially available testers

Designation	e. g. make, order no.
Used without adapter	
Digital testers	Bosch, ETD 019.02 or MOT 350/500/501
	Sun, DIT 9100
	AVL, Diesel-Tester 873
Used with adapter	
Digital testers	Bosch, MOT 001.03
Lambda tester	Bosch, KDJE-P 600
(only for EDS)	Hermann, L 115




Connection diagram for testers with adapter

001	Digital tester	017	RI generator
010	Adapter	021	TDC pulse generator
011	Trigger clamp	2	Governor
015	Test cable with connector	2i	RI generator pin
016	Diagnostic socket	59	TDC generator pin


Testing, adjusting engine

- 1 Check coolant level, correct if necessary.
- 2 Check engine oil level, paying attention to condition of oil (visual inspection).
- $3\,$ $\,$ Remove air filter element (visual inspection), and install.
- 4 Connect testers (013, 001, 017) according to connection diagram.
- 5 Connect pulse generator (021).
- 6 Check accelerator control for ease of movement and condition. Lubricate bearing points, relay levers and ball sockets.

7 Check full throttle stop from accelerator pedal; adjust at adjusting screw (229) if necessary.




Engine 602.96




Engine 603.96

8 Check idle stop.

The spring plate (226) of the Bowden cable (230) must be resting against the compression spring (227) free of tension.




Engine 602.96



Engine 603.96

Adjust Bowden cable (230) with adjusting nut (232) from the car interior, if necessary.




- 9 Test voltage at battery. Specification: at least 11.5 V.
- 10 Raise engine to operating temperature (coolant temperature approx. 80 $^{\circ}$ C).
- 11 Switch off air conditioner or automatic climate control.

Test idling speed.

Unplug 2-pin coupling at actuator, plug in. Set idling speed by slackening locking nut (arrow).

Engine	Idle speed in rpm with control	Idle speed rpm connector at actuator unplugged without control
602.96 manual transm.	740±20	690±40
602.96 automatic transm.	680±20	620±40
603.96	630±20	570±40
	680±20 1)	620±40 1)
603.970	630±20	570±40
603.971	610±20	560±40
-		



1) 4MATIC with manual transmission.

Test start of delivery dynamically, read off on digital tester (07-8244).

- 12 Test "max. speed" without engine load.
- 13 Test injection timing device without load.
- 14 Test electronic diesel system, see (07.1-1120).